

NRCS-75-MO-04 -- Henrietta and Highway H Pumping Plants

Estimated Price Range: \$1,000,000 to \$5,000,000

Description of Work:

Construction of two pumping plants at Henrietta & Highway "H" at the Willow-Cravens Creek Watershed District in Ray County, Missouri. Work consists of construction of 2 pumping plants including approximately 2,500 CY of common excavation; 695 CY of earthfill, class A; 200 CY of hand tamped earthfill; 8,054 SF of sheet piling; 1,060 LF of bearing piling; 68.4 CY of Class 4000 concrete; 8,927 LB of steel reinforcement; 126 TN of aggregate surfacing; 430 TN of rockfill; 300 CY of riprap; 137 CY of drainfill; 60,938 LB of structural steel; 626 SF of steel form decking; 2 pre-engineered metal buildings with electrical systems; one 13,000 GPM pump with electric drive motor; one 20,000 GPM pump with electric drive motor; one 25,000 GPM pump with electric drive motor; 133 LF of steel discharge pipe for 13,000 GPM pump; 126 LF of steel discharge pipe for 20,000 GPM pump; 126 LF of steel discharge pipe for 25,000 GPM pump; 3 flap gates for the discharge pipes; 670 SF of galvanized floor grating; 473 LF of 72" chain link fence; 11 LF of 48" chain link fence; 3.0 AC seeding and mulching; 750 SY geotextile. Solicitation will be available at <http://www.fedbizopps.gov> on or about April 14, 2004. Requests for hardcopy must be in writing. Fax your requests to 573-876-0914.

No notice will be given for amendments or modifications to this solicitation.

Site Showing:

See solicitation for details.

BidOpeningTime: 5/17/2004 10:00:00 AM

To request a copy of this solicitation, submit your name and address

Renee Gardner, Contracting Officer
USDA-NRCS
601 Business 70 West, Suite 250
Columbia, MO 65203
Telephone: 573-876-9374
FAX: 573-876-0914
renee.gardner@mo.usda.gov